

## Segmental Retaining Wall– Anakeesta Gatlinburg, TN



### Services Provided:

- **Retaining Wall Design**– CAD drawings with detailed specifications and recommendations.
- **Construction Observations**– Observed soil bearing conditions and wall construction

This project, completed in 2019, consisted of the design and construction of a RediRock block segmental retaining wall at Anakeesta. The wall was approximately 115 ft. long with a maximum height of 22.5 ft. This wall featured the use of RediRock's 96" XL block.

ETS provided a set of plans and recommendations consisting of bearing conditions, drainage, block placement, grid lengths and spacing, and backfilling procedures.

ETS Project Manager: Chad Smock, P.E.  
E-mail: [csmock@ets-tn.com](mailto:csmock@ets-tn.com)  
Website: [www.ets-tn.com](http://www.ets-tn.com)

Knoxville Office  
Phone: (865) 474-6200

Sevierville Office  
Phone: (865) 428-4468